

STOWA REPORT

# Biological Phosphorus Removal

---

Manual for design and operation

P.M.J. Janssen  
K. Meinema  
H.F. van der Roest

DHV Water BV,  
Amersfoort, the Netherlands



**IWA**  
Publishing

**stowa**

Foundation for Applied Water Research

# Contents

---

<i>Preface</i>	<i>ix</i>
Summary	1
1 Introduction	7
1.1 The need for a new method of biological phosphorus removal	7
1.2 The goal of this manual	7
1.3 Historical background	8
1.3.1 First observations: ‘luxury uptake’	8
1.3.2 Microbiological research: the <i>Acinetobacter</i> genus	8
1.3.3 Barnard and South Africa: first practical configurations	9
1.3.4 Rensink: the relationship between P release and P uptake	9
1.3.5 The development of a biochemical model	9
1.3.6 The role of nitrate: more or less favourable?	10
1.3.7 Modelling: stepwise development	10
1.3.8 Bio-P in the Netherlands: broad implementation	10
1.4 Advantages and disadvantages of biological P removal	11
1.4.1 Advantages of the bio-P process	11
1.4.2 Disadvantages of the bio-P process	12
2 Background of the bio-P process	15
2.1 Introduction	15
2.2 Qualitative description of the bio-P process	15
2.3 Microbiological background of phosphate-accumulating organisms	17
2.4 Biochemistry of the bio-P process	18

2.5	Incorporation of phosphate in sludge	20
2.6	P release and P uptake tests	22
2.7	Environmental factors for the bio-P process	26
2.7.1	Temperature	26
2.7.2	pH	27
2.7.3	Influent composition	27
2.7.4	Nitrate/oxygen	29
2.7.5	Sludge loading/age	31
2.7.6	Anaerobic conditions/contact time	31
3	Design models for bio-P systems	33
3.1	Static models	33
3.1.1	Introduction	33
3.1.2	Empirical models	33
3.1.3	Henze, Scheer and Smolders' methods	34
3.2	Dynamic models	36
3.2.1	Introduction	36
3.2.2	Sub-processes of bio-P in a dynamic model	37
3.2.3	Comparison of dynamic models	39
4	Configurations of bio-P	41
4.1	Introduction	41
4.2	Configurations of bio-P	42
4.2.1	Mainstream process or sidestream process	42
4.2.2	Continuous or discontinuous anaerobic phase	43
4.2.3	Presence of separate denitrification volume	43
4.2.4	UCT or Phoredox configuration	44
4.2.5	Configuration of aeration tank	44
4.3	Bio-P and pre-acidification	44
4.3.1	Introduction	44
4.3.2	Sludge hydrolysis/acidification in the treatment process	45
4.3.3	Production of VFA in relation to process conditions	46
4.3.4	Other aspects of primary sludge acidification, and its relationship to other processes	47
4.4	The bio-P process and sludge settling	48
4.4.1	Introduction	48
4.4.2	Wash-out of suspended solids	48
4.4.3	Anaerobic conditions in the secondary settler	49
4.4.4	Relation with sludge settleability	50
4.5	The bio-P process and sludge treatment	51
4.5.1	Introduction	51
4.5.2	Phosphate release during sludge treatment	53
4.5.3	Dutch and foreign experience	54
4.5.4	Measures to prevent phosphate recycling from sludge treatment	55
4.6	The bio-P process and supplementary chemical P removal	57
4.6.1	Introduction	57
4.6.2	Supplementary chemical phosphorus removal versus biochemistry of the bio-P process	57
4.6.3	Point of additional dosing	57
4.7	Control aspects of bio-P	59

5	Bio-P treatment systems	61
5.1	The selection of WWTPs	61
5.2	Amersfoort WWTP	62
5.2.1	Process description	62
5.2.2	Design and dimensioning	64
5.2.3	Design aspects of bio-P	65
5.2.4	Results (from non-disturbed period)	66
5.3	Katwoude WWTP	68
5.3.1	Process description	68
5.3.2	Design and dimensioning	70
5.3.3	Design aspects of bio-P	71
5.3.4	Results	72
5.4	Goor WWTP	74
5.4.1	Process description	74
5.4.2	Design and dimensioning	75
5.4.3	Design aspects of bio-P	76
5.4.4	Results	77
5.5	Putte WWTP	79
5.5.1	Process description	79
5.5.2	Design and dimensioning	79
5.5.3	Design aspects of bio-P	80
5.5.4	Results	81
5.6	Hardenberg WWTP	83
5.6.1	Process description	83
5.6.2	Design and dimensioning	84
5.6.3	Design aspects of bio-P	85
5.6.4	Results	86
5.7	Elburg WWTP	89
5.7.1	Process description	89
5.7.2	Design and dimensioning	90
5.7.3	Design aspects of bio-P	91
5.7.4	Results	92
5.8	Oud-Beijerland WWTP	94
5.8.1	Process description	94
5.8.2	Design and dimensioning	94
5.8.3	Design aspects of bio-P	96
5.8.4	Results	97
5.9	Venlo WWTP	99
5.9.1	Process description	99
5.9.2	Design and dimensioning	100
5.9.3	Design aspects of bio-P	102
5.9.4	Results	103
5.10	Waarde WWTP	105
5.10.1	Process description	105
5.10.2	Design and dimensioning	106
5.10.3	Design aspects of bio-P	107
5.10.4	Results	108

5.11	Zetten WWTP	110
5.11.1	Process description	110
5.11.2	Design and dimensioning	111
5.11.3	Design aspects of bio-P	112
5.11.4	Results	113
5.12	Maastricht-Boscherveld WWTP	115
5.12.1	Process description	115
5.12.2	Design and dimensioning	116
5.12.3	Design aspects of bio-P	117
5.12.4	Results	118
5.13	Haarlem-Waarderpolder WWTP	121
5.13.1	Process description	121
5.13.2	Design and dimensioning	121
5.13.3	Design aspects of bio-P	122
5.13.4	Results	124
6	Further information on the WWTPs described in Chapter 5	127
6.1	Verification of the static bio-P model with results from full-scale testing	127
6.1.1	Verification based on average operation results: introduction	127
6.1.2	Verification of higher process temperatures and nitrate contents: introduction	129
6.1.3	Conclusions on the applicability of Scheer's bio-P model	130
6.2	Analysis of the P content of effluent, P removal and P stability	131
6.2.1	P content of effluent, and P removal: based on average results	131
6.2.2	Stability of P removal: introduction	134
6.3	Analysis of sludge treatment, P content of the sludge, sludge settling, control aspects and anoxic P removal	137
6.3.1	Bio-P and sludge treatment	137
6.3.2	Bio-P and P content of the sludge	138
6.3.3	Bio-P and sludge settling properties	139
6.3.4	Bio-P and control aspects	140
6.3.5	Bio-P and anoxic phosphorus removal	141
6.4	Conclusions	141
7	Design and optimisation of bio-P plants	143
7.1	Introduction	143
7.2	Design of the bio-P process	143
7.3	Optimisation of the bio-P process	147
	Bibliography	151
	Appendix 1	155
	Appendix 2	157
	Appendix 3	161
	Appendix 4	165
	Appendix 5	173
	Appendix 6	181
	Appendix 7	195
	Index	207