

**AUTHORS: D J BALMFORTH\***  
R J HENDERSON

APRIL 1988

ER 304E.

**A GUIDE TO THE DESIGN OF  
STORM OVERFLOW STRUCTURES:**

\* Department of Civil Engineering,  
Sheffield City Polytechnic


DISTRIBUTION: Unrestricted

Price: £50.

Technical enquiries to, and further copies available  
from:

WRc Engineering  
Frankland Road  
Blagrove  
P O Box 85  
Swindon  
Wiltshire SN5 8YR

Tel: (0793) 511711  
(0793) 511712  
Telex: 449541



## CONTENTS

	PAGE
SUMMARY	(i)
1. INTRODUCTION	1
1.1 A REVIEW OF STORM SEWAGE OVERFLOW PRACTICE	1
1.2 POLLUTING EFFECTS OF STORM SEWAGE OVERFLOWS	4
1.3 PROBLEMS WITH EXISTING OVERFLOWS	5
1.4 STORM SEWAGE OVERFLOWS AND SEWERAGE REHABILITATION	8
2. DESIGN ISSUES	15
2.1 OBJECTIVES OF STORM SEWAGE OVERFLOW OPERATION	15
2.2 IMPACT ON RECEIVING WATERCOURSES	16
2.3 RELIEVING SEWER SYSTEM OVERLOAD	17
2.4 SEPARATION OF GROSS POLLUTING SOLIDS	18
2.5 THE USE OF STORAGE	19
3. HYDRAULIC CONTROL AT STORM SEWAGE OVERFLOWS	20
3.1 HYDRAULIC PROPERTIES	20
3.2 ORIFICE PLATE THROTTLES	21
3.3 ADJUSTABLE PENSTOCKS AND GATES	22
3.4 THROTTLE PIPES	23
3.5 VORTEX REGULATORS	25
4. DESIGN OF STORM SEWAGE OVERFLOW STRUCTURES	30
4.1 THE HIGH SIDE WEIR OVERFLOW	30
4.2 STILLING POND OVERFLOWS	31
4.3 THE VORTEX OVERFLOW WITH PERIPHERAL SPILL	33
4.4 DESIGN OF THE OVERFLOW OUTLET PIPE	34
4.5 THE USE OF SCREENS	34
4.6 ACCESS AND MAINTENANCE	36
5. CONCLUSIONS AND FUTURE DEVELOPMENTS	43
5.1 CONCLUSIONS AND RECOMMENDATIONS	43

	PAGE
5.2 DEVELOPING DESIGNS	44
5.3 IN-SITU MONITORING OF STORM SEWAGE OVERFLOWS	45
5.4 REAL TIME CONTROL	46
6. REFERENCES	47
ACKNOWLEDGEMENTS	50
APPENDIX I Design of High Side Weir Overflow	51
APPENDIX II Design of Stilling Pond Overflow	56
APPENDIX III Design of Vortex Overflow with Peripheral Spill	61